



- **Willow Creek Fish Barrier**, \$460,000 *Summer of 2016* for New Mexico Game and Fish Department in the White Mountains of Southwestern New Mexico, as Site Superintendent and QCM for Tyonek Contractors on 81' wide x 20' tall concrete weir dam with large rip rap and use of an Aqua Dam for the water diversion while under construction.



- **Roberts Creek Culvert Replacement**, \$420,000 *Spring of 2015* for Tyonek Community Development Corporation in Tyonek, Alaska, as PM, QCM, SSHO and Site Superintendent for Tyonek Contractors on 80' long with a 17' diameter culvert consisting of 140 pieces assembled in place with rock baffles and rip rap built into the bottom area of the culvert. Two 36" diameter culverts that were failing were replaced by this larger culvert. And the road was reinstalled and compacted for heavy trucks hauling oil rigs and other large hauls.